

Hydro-elastic coupling effect on the dynamic global response of a spar-type floating offshore wind turbine

Cesar. Aguilera ¹, Romain. Ribault ², Jerome. De-Lauzon ³, and Adrien. Hirvoas ²

¹Sercel, 16 Rue du Bel air, 44470 Carquefou, France

²France energies Marines, 525 Av. Alexis de Rochon, 29280 Plouzané, France

³Bureau Veritas, 1 place Zaha Hadid, 92400 Courbevoie, France

Correspondence: Cesar. Aguilera (cesar.aguilera@sercel.com)

Abstract. Designing floating wind turbine systems requires integrated load assessments (ILA) using fully coupled hydro-servo-aero-elastic models. In most cases, floater hydrodynamics are represented using potential flow models for mooring system design and motion estimation, while the floater itself is typically assumed to behave as a rigid body. However, this assumption can significantly affect tower eigenfrequency calculations, especially for large floaters. In this study, we investigate these effects using in-situ sensor data from the Zephyros 2.3 MW spar wind turbine. We present a methodology to accurately determine tower's eigenfrequencies. A rigid floater model without added mass leads to an average error of 38% compared to measured tower modes. Including hydrostatic added mass reduces the error to 28%. Further incorporating floater flexibility decreases the error to 5%, and accounting for blade flexibility lowers it to just 3%. These discrepancies highlight the importance of refining the hydro-servo-aero-elastic model to align with eigenfrequencies derived from finite element hydro-structural analyses. We present potential model adjustments, assess their impacts, and demonstrate the updated validation process.

1 Introduction

Offshore wind energy has experienced rapid growth over the past decade, with capacity tripling between 2012 and 2022. During this period, an average of 55 GW of new wind capacity was added annually, reaching as much as 75 GW in 2022 alone (IRENA , 2023). According to IRENA (2023)'s 1.5° scenario, wind energy is expected to become one of the largest sources of electricity worldwide, with an estimated 10,300 GW of installed capacity by 2050.

Despite this expansion, the sector continues to face the challenge of a relatively high levelized cost of energy (LCOE) compared to other power generation sources. However, collaborative research, supportive government policies, and advances in large-scale asset production have significantly reduced the LCOE of Floating Offshore Wind Turbines (FOWTs), making them increasingly cost-competitive (WindEurope , 2020).

One strategy for cost reduction is to increase the power output of individual turbines. This approach, however, also requires a proportional increase in the overall structural size. As floating foundations scale up, they must be designed to remain stable and flexible under more demanding conditions. The design of support structures for FOWTs is particularly challenging due to the complex physical phenomena involved and the harsh marine environments in which they operate (European Commission , 2019). Consequently, the continuous trend toward larger and more powerful turbines raises new concerns for the engineering and design community.

Currently, only a few FOWTs are operational. Zephyros (shown in figure 1), is one them. This wind turbine is located 11 km far from the coast of Norway and owned by Unitech. It is the first multi-megawatt floating turbine in the world (Skaare et al. , 2014). The first numerical model of Zephyros was presented in the work of Skaare et al. (2007). In this work, the structure was modeled using a coupled simulation based on two different software's, SIMO/RIFLEX and HywindSim, developed by Marintek and Risø National Laboratory respectively. Both simulators solve their own dynamic equilibrium equations in time domain. A scaled set of tests cases were carried out by Ocean Basin Laboratory at Marintek with the objective to compare the results of an integrated coupled simulation tool outputs with experimental data. A good agreement was shown between simulation and measurement data.

Many studies employing aero-hydro-servo-elastic simulations of FOWTs (e.g., (Curfs , 2015; Cheng et al. , 2015; Zhang et al. , 2020)) account for tower and blade flexibility. However, when the focus is on mooring design or platform motion, floater hydrodynamics are often modeled using potential flow theory. While these models capture hydrodynamic loading with reasonable accuracy, they generally assume the floater to be rigid. This assumption not only



Figure 1. Zephyros, the world's first multi-megawatt FOWT UNITECH (2022). Credits: Unitech Energy Group

precludes the estimation of internal loads within the floater but also influences the calculation of tower eigenfrequencies, which in turn may affect predictions of the tower's dynamic response.

The importance of considering floater flexibility in global dynamic responses has been emphasized in recent studies. For example, Li et al. (2023) investigated a 15 MW semi-submersible wind turbine, highlighting the influence of structural flexibility on its dynamic behavior. Similarly, Borg et al. (2016) proposed an approach to incorporate large-volume substructure flexibility using an iterative coupling between the radiation-diffraction solver WAMIT and the aeroelastic code HAWC2 for a spar-type platform. Their study compared the global responses of rigid and flexible models, showing that accounting for flexibility yields more accurate sectional load predictions.

As shown in the literature, the effect of floater flexibility has been addressed for different types of floating support structures and wind turbine sizes. According to DNV-RP-0286 (DNV-GL , 2019), the assumption of rigid-body

Table 1. Wind turbine characteristics.

Parameter	Value/Unit
Turbine power	2.3 MW
Turbine weight	138 tons
Draft hull	100 m
Nacelle height	65 m
Rotor diameter	82.4 m
Water depth	220 m
Mooring	3 lines
Diameter at water line	6 m
Diam. submerged body	8.3 m
Rotor speed	6 – 18 rpm
Wind speed range	3 – 25 m/s

**Figure 2.** Sensor position along the tower.

behavior may be acceptable in certain cases, provided it can be demonstrated that floater flexibility does not significantly influence the turbine’s response. Similarly, NR572 (Bureau Veritas , 2015) states that hydro-elasticity should be considered when relevant. However, despite these references, there is currently no clear or unified guidance on best practices for assessing the validity and applicability of the rigid-body simplification during the design phase of floating substructures.

This article details a methodology to accurately calculate tower eigen-frequencies at design stage and integrate floater flexibility effect into the aero-hydro-servo-elastic simulations. We demonstrate the impacts of floater rigid body assumption on tower eigenfrequency calculation, using in-situ sensor data from the Zephyros 2.3 MW spar wind turbine. Section 1.1 briefly introduces the Zephyros wind turbine. In Section 2.1, we describe the measurement campaign and the estimation of tower eigenfrequencies, among other dynamic parameters, using the S-Morpho measurement system. In Section 2.2, we describe the numerical models. The subsection 2.2.1 provides some theoretical background on the hydro-structural model used for modal analysis and reference calculation of the tower eigenfrequencies. Then, in Section 2.2.2, we describe the initial aero-hydro-servo-elastic simulation model implemented in OpenFAST. In Section 2.2.3, is presented the potential simulation model adjustments, discussing their limitations and impacts. For the tower’s eigenfrequency calculation from time-domain simulation results, we used an Operational Modal Analysis (OMA) described in Section 2.2.4. In section 3 we describe the load cases we used to run the aero-hydro-servo-elastic models in order to assess tower eigenfrequency in time domain simulation and identify a potential modification of the global dynamic tower response . Section 4 is dedicated to the discussion and the presentation of the results.

1.1 Description of Zephyros floating wind turbine

Unitech Zephyros is a floating spar offshore wind turbine originally installed as Hywind Demo by Equinor (Statoil) at approximately 11 kilometres of the west coast of Karmøy (Norway). The floater is based on a cylinder shape submerged vertically and connected to a steel tower. Having a spar-type substructure, the structure is stabilized due to the long distance between the center of gravity and center of buoyancy. This system is supporting a Siemens 2.3 MW wind turbine with a rotor diameter of 82.4 meters.

The system is fixed to the seabed by three mooring lines consisting of hybrids wires and clump weights. The length of each line is approximately 800 metres. The hull is ballasted with gravel and water. The main particulars of Zephyros are given in Table 1. For a detailed description of the structure refer to the work of Godø (2013).

2 Methodology

2.1 Measurements performed on 2.3MW Zephyros wind turbines

Dynamic and static measurement data were collected continuously over two years within the framework of the DIONYSOS project using the S-Morpho system. The sensor outputs include three-axis accelerations, magnetic field, and temperature at a sampling frequency of $40Hz$. Six sensors were installed along the Zephyros tower in May 2022, approximately 30° west-north.

Their positions were at 17, 33, 41, 49, 57, and 63 m above sea level. The local sensor reference frame was aligned with the tower’s reference frame: the X-axis corresponds to fore-aft movement, the Y-axis to side-to-side movement, and the Z-axis to vertical movement.

Figure 2 shows the first two sensors installed on the tower. As the tower is made of steel, all sensors were fixed by two powerful magnets per unit. A general view of the positioning is provided in figure 3. For further details about the sensor system, refer to Redoute (2020).

2.1.1 Modal Identification of Zephyros Tower From Measurements

The simulation of the dynamic behavior of a wind turbine is highly dependent on the accuracy of its numerical model. To ensure the model correctly reproduces the dynamic response of the asset, calibration must be performed using reliable experimental data. In this work, the selected experimental data for calibration were the global modal parameters.

The Zephyros wind turbine is equipped with a yaw system, which allows the nacelle to rotate and remain oriented toward the wind direction. This feature adds complexity to the modal analysis, as the structural modal deformations depend on the nacelle orientation (Oliveira et al. , 2018). To address the challenge of combining the moving reference frame of the nacelle with the fixed reference frame of the tower, a coordinate transformation was applied. The transformation used the nacelle orientation angle, obtained from the SCADA data provided by Unitech Energy Group.:

$$\begin{bmatrix} x'(t, \theta) \\ y'(t, \theta) \\ z'(t, \theta) \end{bmatrix} = R(\theta) \cdot \begin{bmatrix} x(\theta) \\ y(\theta) \\ z(\theta) \end{bmatrix} \quad (1)$$

Where the variables x and y contain the raw acceleration data, variables x' and y' are the new transformed accelerations and corresponds to the yaw angle θ of a 10 min averaged. $R(\theta)$ is the three axes matrix rotation.

This coordinate transformation enables the projection of the measured acceleration signals into the fore-aft and side-to-side directions of the wind turbine — i.e., the directions parallel and perpendicular to the rotor plane, respectively. The transformation was applied to the entire dataset collected during December 2022, allowing comparison with SCADA data acquired for the same period.

After performing the transformation, reference modal parameters were estimated from a 20-minute interval when the wind turbine operated under rated conditions. The environmental parameters corresponding to this operating condition are summarized in table 3.

Subsequently, the transformed acceleration data were continuously processed for the entire month using Operational Modal Analysis (OMA) techniques for wind turbine structures when external excitation cannot be measured (van Vondelen et al. , 2022). In order to estimate and track the modal frequencies and mode shapes over time, the covariance-driven Stochastic Subspace Identification (SSI-COV) method was employed (Masjedian et al. , 2009), using six reference channels and a time lag of 10 seconds. The



Figure 3. Graphic representation of the finite element model used in Homer software

analysis provided parametric estimations within 20-minute moving windows. To ensure the correct modal shape tracking over time, the Modal assurance criterion (MAC) was used to assess the correlation between the continuously estimated and reference mode shapes (Pastor et al. , 2012). When the MAC value exceeded 0.9, the corresponding mode shape was retained as a valid tracked mode.

Figure 4 illustrates the temporal evolution of the second fore-aft and side-to-side tower modes during December 2022, shown by the pink and red lines, respectively. The black line represents the rotor rotational speed in RPM, derived from SCADA data. This figure highlights the influence of rotor rotation on the tower's modal frequencies. The emerged frequencies of the structure are shown in table 4. A more detailed description about the computational methodology can be found in the document of SERCEL (2024).

2.2 Numerical models

In the following subsections, the calculation methodology for each software tool is briefly described. It should be noted that Homer was employed as the offshore modal analysis tool, solving the classic equation of motion (equation 3). For coupled dynamic time-domain simulations of the wind turbine, an OpenFAST model was developed and tested. A summary of the two numerical model characteristics is given in table 2. A more detailed description is given in the following sections.




Figure 4. Plot of the second tower natural frequency tracking correlated with the rotor rotation during December 2022

2.2.1 Hydro-Structure Model To Perform Tower's Eigenfrequency Reference Calculation

To calculate the reference eigenfrequencies of the tower, the analysis was carried-out in Homer, an Hydro-structure software with modal analysis capability developed by Bureau Veritas (Malenica et al. , 2013). The model implemented in Homer describes the full mechanical FOWT system and is derived from an ANSYS model (figure 3). The floater and tower are build with shell elements. Rotor Nacelle Assembly is modelled as a mass element, connected to the tower rigidly. Blades are also modelled, either as flexible beam elements, or by just considering their inertia.

The hydro-elastic analysis performed in Homer relies on the decomposition of the structural response of the floating wind turbine on its N first dry vibration modes. Instead of solving a 6-by-6 linear problem, the dimension of all matrices (mass, added mass, stiffness) is increased to $6 + N$.

The first step in the coupled analysis is therefore a dry modal analysis of the structure. When the flexible modes have been chosen, the hydrostatic stiffness is computed for the N vibration modes, as well as for the six rigid body motions (surge, sway, heave, roll, pitch, and yaw). The hydrodynamic radiation boundary value problem is then solved by Hydrostar for the $6 + N$ modes, and the added mass matrix is then assembled. Finally, the wet eigen-modes and frequencies are computed. The method is rather well known and has been the subject of many scientific publications (Malenica et al. , 2008). The pre-stressing at hydrostatic equilibrium is not considered in this analysis; its influence is assumed to be small.

Bureau Veritas Hydrostar software is used to solve the radiation boundary value problems for the rigid body motions, as well as for the vibration modes. For each vibration mode, the additional body boundary condition becomes:

Table 2. Model main characteristics in function of the numerical software.

software	Flexible floater	Rigid nacelle	Flexible blades
Homer	✓	✓	x/✓
OpenFAST	x	✓	✓

$$\frac{\partial \varphi_{Rj}}{\partial n} = \mathbf{h}^j \cdot \mathbf{n} \quad (2) \quad 35$$

Where φ_{Rj} is the radiated velocity potential for mode j and \mathbf{h}^j is the shape of mode j , interpolated from the finite element model to the hydrodynamic mesh. Once all radiation boundary value problems (6 rigid motions and N elastic modes) have been solved, the radiation pressures are computed at the center of the finite elements, and integrated to compute the added masses. The motion equation can then be written as (after removing the excitation forces and radiation damping):

$$(-\omega^2[M + A(\omega)] + [K + C])\{\xi\} = 0 \quad (3) \quad 45$$

With $[K]$ the structural stiffness, $[C]$ the hydrostatic stiffness, $[M]$ the structural mass, $[A(\omega)]$ the added mass and $\{\xi\}$ the vector of modal amplitudes.

For each frequency ω , the inverse of the total mass (including added mass) is computed and multiplied by the total stiffness. The resulting matrix is finally diagonalized for each frequency to find the wet eigen-frequencies and eigenvectors. For each eigen-mode computed by the diagonalisation, the vibration frequency is obtained when the eigen-frequency matches the frequency used for the added mass.

$$[M + A(\omega)]^{-1}[K + C]\{\xi\} = \omega^2\{\xi\} \quad (4)$$




Figure 5. Schematic overview of the FOWT modeling approach in OpenFAST.




Figure 6. Schematization of the methodology followed in this study.

2.2.2 Initial Aero-Hydro-Servo-Elastic Simulation Model

OpenFAST (FAST stands for Fatigue, Aerodynamics, Structures, and Turbulence) is an open-source engineering code distributed by the National Wind Technology Center (NWTC) (Jonkman et al. , 2005). This code is a nonlinear time-domain simulator that employs a combined modal and multibody structural-dynamics formulation. In our research, the numerical representation of the Zephyros system has been implemented within OpenFAST. This model assumes a rigid platform but accounts for the tower's flexibility, see Figure 5. The structural, hydrodynamic, and aerodynamic properties of the FOWT were configured based on publicly available documents and generic wind turbine data interpolation. The key properties defined include inertial characteristics of the nacelle, lift and drag profiles of the airfoil, along with mass and structural-elastic properties at various blade locations, inertial and structural-elastic characteristics of the drive train, mass and structural-elastic properties at specific tower locations, from the waterline to the tower's top, and inertial properties of the rigid spar.

To prevent drifting, the Zephyros platform is anchored to the seabed using three separate catenary mooring lines attached to anchors at the seafloor. For the numerical representation of mooring line dynamics, we used MoorDyn, a dynamic lumped mass model within OpenFAST (Hall , 2015). This numerical modeling methodology leverages this model's capability to represent multi-segmented mooring lines, comprising diverse elements such as chains, unsheathed spiral ropes, and additional clump weights, as outlined in Hirvoas (2022). The latest version of MoorDyn enables modeling

two-leg bridles, significantly improving the yaw natural period from previous versions (Hall , 2020).

Incorporating hydrodynamics into the numerical simulation requires accurately defining incident wave characteristics and hydrodynamic loading representations (Molin , 2023). Within this OpenFAST framework, HydroDyn is the module designed to calculate these hydrodynamic loads in the time domain (Jonkman et al. , 2014). To obtain the hydrodynamic loads acting on the rigid body platform, a pre-computation step using radiation-diffraction software with a second-order loading module is necessary to solve different hydrodynamic theories. Finally, in our full-scale study, we calibrated the mooring radius and the platform's displaced volume to match the system's natural periods with low relative errors, as evaluated using in-situ data.

Additionally, we adapted the ROSCO NREL controller, as described in Abbas et al. (2022), to the simulation model and conducted different dynamic load cases, comparing them with field measurements. The results show that the floating platform movements closely match the measured data, indicating good agreement as shown in Hirvoas (2022).

2.2.3 Possible aero-hydro-servo-elastic model modification and impacts

When modification of the aero-hydro-servo-elastic model is required to align the simulated tower eigenfrequencies with the measured or calculated values, several approaches can be applied. A first option is to model the floater as a flexible body, using a beam-element discretization and distributing the hydrodynamic loading over each element. This provides access to the internal loads of the floater at the chosen discretization scale. Two types of hydrodynamic models can be employed :

1. Distributed potential flow hydrodynamic model.
2. Distributed Morison elements.

Thomsen et al. (2021) and Xu et al. (2019), applied a full Morison approach for the hydrodynamic model and beam elements for mechanical model of the floater. Such approach can lead to satisfactory FOWT global model with floater flexible models. However, Morison hydrodynamics model has its own limitations (Leroy et al. , 2021) and coefficients are not available for all floater shapes which makes the approach not applicable for some floater designs (Guignier et al. , 2016).

To overcome these constraints, several initiatives have investigated equivalent approaches that combine potential-flow theory with flexible floater modeling. These methods leverage the multi-body or additional generalized modes capabilities of radiation-diffraction software (e.g., WAMIT, HydroStar, Diodore) in combination with beam-element aero-hydro-servo-elastic solvers (e.g., OrcaFlex, Deeplines, SIMA). In such frameworks:




Figure 7.

- The radiation diffraction software calculates several hydrodynamic database (HDB) on a floater discretisation equivalent to the mechanical model discretization.
- The floater is mechanically modeled as an assembly of beam elements in aero-hydro-servo-elastic software and for each beam element, the corresponding HDB is associated.

This type of approach was applied to the Ideol’s floater, using Ansys Aqwa as the radiation diffraction software and Orcaflex as the aero-hydro-servo-elastic software (Guignier et al. , 2016); In their work, a multibody approach was implemented in Aqwa, where the floater was discretized into several compartments. HDBs were then computed, including the hydrodynamic interactions between compartments. However, to prevent divergence of the calculations, the compartments had to be artificially separated within the Aqwa code.

A similar but different approach was applied to a spar platform, supporting the DTU 10 MW by Xiaoming et al. (2023); and a three-column semi-submersible floaters by Chenyu et al. (2017) and by Li et al. (2023). They all used Wamit as a Radiation-Diffraction software and an in-house code to integrate panel pressure per floater sub-structure to compute the added mass, damping and excitation forces with a discretization adapted to the mechanical model of the floater.

In the above cited approaches, hydrodynamic interactions between sub-structures are taken into account, but the hydrostatic/hydrodynamic loads are not influenced back by floater flexibility. Chenyu et al. (2017) acknowledged that the influence of the inertia loads and hydro loads induced by the flexible modes of the hull shall be investigated in future. To account for deformable modes of a floater contribution into hydrodynamic loads, within a small deformation assumption, Borg et al. (2016) proposed an iterative procedure between aero-hydro-servo-elastic (HAWC2) and WAMIT. Additional generalized modes calculation option may also be used de Lauzon (2024) and are available in Homer software. Xiaom-

ing et al. (2023) performed an experimental validation such an hydro-structural coupled model, demonstrating that internal floater loading estimations were more accurate with a distributed potential flow hydrodynamic model rather than with a Morison hydrodynamic model.

When the above approaches cannot be implemented, other options are available :

1. Prolongate the tower mechanical model with a virtual element inside the floater and calibrate the mechanical properties to match the tower eigenfrequencies.
2. Modify the global stiffness modal parameter in OpenFast, such an option is available inside the Elastodyn file

In our case, the chosen option was to modify the global tower stiffness. The OpenFAST model employed did not include the SubDyn module, which would have enabled the representation of the tower’s prolongation below the floater–tower interface. Given the significant mismatch in eigenfrequencies, adding a small structural element at the tower base was not considered a viable option. It is worth noting, however, that recent updates to the HydroDyn and SubDyn modules now include capabilities for modeling flexible floaters.

2.2.4 Verification tool of simulated tower frequencies and shapes

To verify the tower eigenfrequencies from the aero-hydro-servo-elastic setup against those obtained from the hydro-structure calculation model, a modal analysis is required. This comprehensive model is primarily used for time-domain simulations, where most of the physics are nonlinear. Consequently, a specific linearization of the state-space representation is necessary to perform eigenanalysis. Most software tools include built-in modules for this purpose. Here, two options were available:

Table 3. Load cases characteristics of 1 hour average values. Low condition of 02/12/2022 at 3 p.m. And Rated condition of 06/12/2022 at 10 p.m.

Load case	Low condition	Rated condition
Wave height [m]	1.36	3.3
Wave direction [°]	273	336
Wave period [s]	13	8
Wind speed [m/s]	1.92	15.1
Wind direction [°]	70.88	354.7

- the use of the linearization functionality included in the OpenFAST open-source code
- running OMA techniques on the OpenFAST output acceleration data.

Even though the OpenFAST functionality has been widely used and verified for FOWTs as demonstrated in Johnson et al. (2019), in this study the validation of the natural frequencies and shapes was estimated via OMA already used when estimating the modal parameters of measured data, described in section 2.1.1.

2.3 Load cases for evaluation of dynamic tower response in time domain calculations

The first stage of the proposed methodology consisted of determining the sensitivity of the tower modes to the floater rigidity. In the second stage, the aero-servo-hydro-elastic model was adapted to account for the floater's flexibility. To achieve this, two main load cases were analyzed in order to investigate the global structural response under both low-wind and rated conditions.

- Low wind condition: wind speed below 12 m/s and significant wave height below 2 m.
- Rated condition: wind speed around 13 m/s and significant wave height of approximately 3.5 m.

The full set of input parameters for these two load cases is presented in table 3. The irregular wave elevation time series were modeled using a JONSWAP spectrum, while the time-varying wind loads were generated with TurbSim, a full-field turbulent wind simulator (Jonkman, 2016).

2.4 Parametric optimization

Once the load cases and the parameters to be optimized were defined, a parametric study was carried out to optimise the global stiffness modal parameter in OpenFAST, available inside the Elastodyn module. This was achieved by the open-access Python package SimuOptuna (Ribault, Romain,

, 2024). The package is based on the Optuna hyperparameter optimization framework (Akiba et al., 2019), specifically adapted for wind turbine simulation tools. The configuration of the optimization routine was as follows:

- Sampler: tree-structured parzen sampler (TPS)
- number of trials: 600
- Loss function : Mean squared error between measured and simulated natural frequencies. Natural frequency identification methodology is described in section 2.1.1.

Since the tower factors vary between 0 and 1, these limits were used to constrain the objective function. Figure 7 illustrates the parametric space and sampling iterative evolution of the first fore-aft tower factor. The color bar indicates the sequential iterations, showing how the objective function value decreases over time. The adjustment factor for the first side-to-side mode was estimated using the same procedure. The optimized values obtained for the first tower modes were 0.397 (fore-aft) and 0.421 (side-to-side). For more details on the parameter optimization process, refer to Ribault, Romain. (2024).




Figure 8. Plot of the measured and simulated natural frequencies of the system (upper figure). Graphical representation of the first fore-aft coupled floater-tower mode (lower image).




Figure 9. Spectrum of the measured and simulated acceleration of the sensor node 4 in function of the fore-aft, side-to-side and vertical directions. The dark blue line represent the measurement, the pink line is the response of the original model and the light blue line the response of the tuned model.

3 Results and Discussion

This section is divided into two parts. Following the schema of figure 6, this section shows the modal sensitivity analysis performed in Homer. In the second part, a spectral analysis of the measured acceleration and the simulation signals is presented.

A 1 hour simulation time was run for each load case in OpenFAST. To avoid the undesired model transient response, the first 300 seconds were eliminated, keeping the equivalent 1 hour simulation when the structure is in its stability position.

3.1 Sensitivity analysis

During this analysis, the effect on the tower modes of the following phenomena and component modeling was evaluated:

- the floater rigidity
- the hydrodynamic added mass
- the flexibility of the blades

This first sensitivity analysis was carried-out in Homer based on the finite element model shown in figure 4. In the reference case, the rotor-nacelle assembly (including the blades) and the floater were assumed to be rigid. To approximate the rigid-floater condition within the HOMER model, the material's Young's modulus was artificially increased from the steel value of $2.1E + 11Pa$ to $1E + 20Pa$. This unrealistic high modulus was used solely to demonstrate

that increasing the floater stiffness in the physically consistent HOMER model causes the system's modal behavior to converge toward the rigid-floater configuration. The adopted value is therefore valid only for the purposes of the present study.

The upper graph in figure 8 presents the natural frequencies of the system. The first six modes correspond to the six degrees of freedom (DoFs) of a floating system. A very good agreement was observed between measured and simulated values, confirming the accuracy of the global mass and stiffness representation. The yaw response exhibited the largest deviation, with a maximum error of 7% while the average error across all six DoFs was approximately 3%. As expected, modeling the floater as rigid showed minimal influence on the low-frequency modes ($1^{st} - 6^{th}$).

In contrast, the floater stiffness strongly affected the tower modes, as seen in the higher-order modes in figure 8. When the floater was considered rigid, significantly larger discrepancies emerged, with errors reaching up to 37% for the second side-to-side tower mode. Conversely, modeling the floater as flexible led to a reduction of the four tower natural frequencies, resulting in much closer agreement with the measured values. A graphic representation of the first fore-aft coupled floater-tower mode shape is shown on the bottom image of figure 8.

In the second analysis, the influence of the hydrodynamic added mass was evaluated. When this additional mass was included, a reduction in the natural frequencies was observed, and the average error decreased to 28% (see column 4 in ta-

Table 4. Summary of the estimated tower natural frequencies from the sensitivity analysis.

Tower mode	S-MORPHO		HOMER		
	Measure	Rigid/dry floater	Hydro added mass	Flexible floater	Flexible blades
1st tower SS [Hz]	0.69	1.10	0.96	0.66	0.70
1st tower FA [Hz]	0.69	1.14	0.98	0.66	0.72

ble 4). Subsequently, when floater flexibility was considered in addition to the hydrodynamic added mass, the tower frequencies showed a more pronounced decrease. This adjustment further reduced the average error 5% (column 5 in table 4).

In the final step, blade flexibility was incorporated, while the hub and nacelle were modeled as rigid. A rigid connection was imposed between the blade roots and the hub, and the distributed blade structural properties were taken from the SIMA model developed by Homb (2013).

Unlike the floater flexibility, the blade flexibility exhibited an opposite effect on the tower modes, leading to a 7% increase in the frequencies compared to the previous results. Nevertheless, this modification improved the overall accuracy, reducing the average error from 5% to 3% (last column in table 4).

3.2 Spectral analysis

It was confirmed that modeling the floater as a rigid body significantly affects the tower natural frequencies of the Zephyros FOWT. Consequently, floater flexibility must be accounted for in the time-domain simulation tool. To achieve this, the tower adjustment factors were modified within the OpenFAST simulator, specifically in the ElastoDyn file. These coefficients multiply the global tower stiffness for the first and second tower modes in both the fore-aft and side-to-side directions. For this study, only the coefficients corresponding to the first tower mode were adjusted.

The coefficient values were determined through a manual trial-and-error procedure to fit the measured frequency spectrum shown in figure 9. The resulting adjustment factors were 0.397 for the fore-aft direction and 0.400 for the side-to-side direction.

To validate the time-domain simulation outputs, four OpenFAST simulations were conducted: two for the low wind condition (using the original and the adjusted model) and two for the rated wind condition. Figure 9 presents the acceleration spectrum comparison for the measured data (dark blue line), the rigid-floater model (pink dashed line), and the tuned model (light blue dashed line) under both operating conditions. The spectra were computed using Welch's Power Spectral Density method in Python.

The simulated dynamic response in the side-to-side direction (middle graph of figure 9) has showed good agree-




Figure 10. First and second tower mode shapes estimated from OpenFAST acceleration output data by OMA routine. Both images depicts the fore-aft direction..

ment within the $0.05 - 3Hz$ frequency range. Notably, the tuned numerical model shifted the original frequency peak from $1.1Hz$ to $0.70Hz$ in both the fore-aft and side-to-side spectra, corresponding to the first tower frequency. This was further validated using the Operational Modal Analysis (OMA) algorithm applied to the acceleration output data, as described in section 2.1.1, and the resulting modal shape is illustrated in figure 10, showing excellent agreement with the first tower mode.

Considering the peak verification, the tuned model accurately captures the first tower mode at $0.69Hz$ and the harmonics due to the rotor rotation, namely the 3P and 6P at $0.83Hz$ and $1.66Hz$ respectively. The model was less accurate in the low-frequency range (0 to $0.05Hz$), likely because second-order hydrodynamic forces were not included in this analysis.

In the fore-aft direction (left images in figure 9), the simulation response exhibited either higher or lower amplitudes than the measured data across the analyzed frequency range. This discrepancy may arise from multiple sources, including uncertainties in sensor position and orientation, and the sensor localization within the numerical model relative to the tower discretization.




Figure 11. Power spectral density of the side-to-side dynamic response of sensor number 4. Rated condition.

As a result of the tuning process, although the dynamic response of the model became closer to the measured data, the global tower stiffness was modified, impacting the overall system behavior. Moreover, the obtained values were considerably low, indicating a substantial reduction in tower rigidity. According to the OpenFAST forum, these tower stiffness tuners are recommended only for small adjustments, with values not smaller than 0.9. Typically, a modification in system stiffness is most evident in the low-frequency content of the response spectrum. Figure 11 illustrates the dynamic response before and after the tower stiffness adjustment. It is apparent that the adjustment primarily affects frequencies below 0.01 Hz . To further assess the influence of the stiffness modification, tower displacements and moments were analyzed. The upper panel of figure 11 shows the displacements at the top of the tower in both the fore-aft and side-to-side directions. As expected, the amplitudes increased with the reduction in tower stiffness. In contrast, the lower panel of figure 11 indicates that the tower-base bending moments within the wave-excitation frequency range ($0 - 0.5\text{ Hz}$) were not significantly affected by the global stiffness reduction.

4 Conclusion

This study investigates the effects of the rigid-floater assumption, the hydrodynamic added mass, and the blade flexibility on the global dynamic response of the 2.3 MW spar-type floating wind turbine Zephyros. In conventional wind turbine structural analyses, it is common to model the floater as a rigid body. However, as wind turbines increase in size to capture more energy, this rigid-floater assumption becomes progressively less valid.




Figure 12. Power spectral density of the tower-top displacements (upper image) and the tower-base moment (lower image)

It was demonstrated that floater flexibility has a substantial impact on the tower modes, with errors reaching up to 37% when compared to measured modal data.

Hydro-servo-aero-elastic simulation tools can incorporate floater flexibility using a Morison hydrodynamic model. When employing potential-flow hydrodynamic models, modern simulation tools are increasingly integrating functionalities to couple distributed hydrodynamic databases with mechanical beam-element representations of the floater.

When it is not possible to implement a flexible floater in the Hydro-servo-aero-elastic model due to software restrictions, it is generally feasible to modify the tower/floater boundary condition and calibrate the tower's eigen-frequencies by adding a massless beam with a well-chosen length and stiffness between the tower and floater. In OpenFAST, one possible solution is adjusting the global tower stiffness factors to properly fit the spectral response to the measured one. We do not recommend using this solution as it modifies the tower's mechanical model itself. However, we implemented it in our case due to limitations of the older OpenFAST version. We observed that this adjustment successfully aligned the tower eigenfrequencies

in the time-domain simulations. It had minimal impact on the low-frequency content of the dynamic response (0–0.01 Hz) but led to increased tower-top displacements, reflecting the effectively reduced tower rigidity. In contrast, the modification had only a minor effect on the tower-base bending moments.

Data availability. Data could be available on demand, in order with the contractual description of DIONYSOS project.

Author contributions. CA: Methodology, Software, Validation, Formal analysis, Investigations, Writing - original draft, Writing - review and editing, Visualization. RR: Methodology, Software, Investigations, Writing - original draft, Writing - review and editing, Project administration. JDL: Methodology, Software, Writing - Original Draft. AH: Methodology, Software, Writing - Original Draft

Competing interests. The authors declare that they have no conflict of interest.

References

- Abbas, Nikhar J and Zalkind, Daniel S and Pao, Lucy and Wright, Alan: A reference open-source controller for fixed and floating offshore wind turbines. 2022.
- Aguilera C. and Desbazeille M.: 20240305 DIONYSOS WP04 Task4.1a Local SHM digital twin on FOWT floater. 2024.
- Akiba, Takuya and Sano, Shotaro and Yanase, Toshihiko and Ohta, Takeru and Koyama, Masanori : Optuna: A Next-Generation Hyperparameter Optimization Framework <https://github.com/optuna/optuna>
- Al-Solihat, Mohammed Khair and Nahon, Meyer: Flexible multi-body dynamic modeling of a floating wind turbine. 2018.
- Allen, C. and Viscelli, A. and Dagher, H. and Goupee, A. and Gaertner, E. and Abbas, N. and Hall, M.D. and Barter, G.: Definition of the UMaine VoltturnUS-S Reference Platform Developed for the IEA Wind 15-Megawatt Offshore Reference Wind Turbine: IEA Wind TCP Task 37. 2020.
- ANSYS: Online Manual. 2024. https://www.caee.utexas.edu/prof/kallivokas/teaching/ANSYS_examples/ansys56theory.pdf
- Berahmand, Kamal and Daneshfar, Fatemeh and Salehi, Elaheh Sadat and Li, Yuefeng and Xu, Yue: Autoencoders and their applications in machine learning: a survey. 2024.
- Bir, G. : User's Guide to BModes (Software for Computing Rotating Beam Coupled Modes). 2007. chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/<https://www.nrel.gov/wind/nwtc/assets/pdfs/bmodes.pdf>
- Borg, Michael and Hansen, Anders Melchior and Bredmose, Henrik: Floating substructure flexibility of large-volume 10MW offshore wind turbine platforms in dynamic calculations. 2016.
- Bureau Veritas: Classification and certification of floating offshore wind turbines. 2015.
- Cheng, Zhengshun and Wang, Kai and Gao, Zhen and Moan, Torgeir: Comparative study of spar type floating horizontal and vertical axis wind turbines subjected to constant winds. 2015.
- Chenyu Luan and Zhen Gao and Torgeir Moan: Development and verification of a time-domain approach for determining forces and moments in structural components of floaters with an application to floating wind turbines. 2017.
- C.P.M. Curfs: Dynamic behaviour of floating wind turbines - A comparison of open water and level ice conditions. 2015. <https://repository.tudelft.nl/record/uuid:f339482a-8e0d-4827-85af-c8cf05b4260f>
- de Lauzon Jérôme: Coupled eigen-frequency analysis of floating wind turbines. 2024.
- DNV-GL: DNV-RP-0286 Coupled analysis of floating wind turbines. 2019.
- European Commission : Summary of the Commission assessment of the draft National Energy and Climate Plan 2021-2030. 2019. https://energy.ec.europa.eu/system/files/2019-06/necp_factsheet_fr_final_0.pdf
- European Commission: Assessment of the final national energy and climate plan of France. 2023. https://commission.europa.eu/system/files/2023-12/SWD_Assessment_draft_updated_NECP_France_2023.pdf
- France Energies Marines: Contractual description – Digital Intelligent Operational Network using hYbrid SensOrs / Simulations approach. 2021.
- Global Wind Energy Council: GLOBAL OFFSHORE WIND REPORT 2023. 2023. <https://gwec.net/wp-content/uploads/2023/08/GWEC-Global-Offshore-Wind-Report-2023.pdf>
- Goodfellow, Ian and Bengio, Yoshua and Courville, Aaron: Deep learning. 2016.
- Guignier, Lucie and Courbois, Adrien and Mariani, Riccardo and Choynet, Thomas: Multibody Modelling of Floating Offshore Wind Turbine Foundation for Global Loads Analysis. 2016.
- Hall, Matthew: MoorDyn user's guide. 2015.
- Hall, Matthew: Moordyn v2: New capabilities in mooring system components and load cases. 2020.
- Haoran Li and Zhen Gao and Erin E. Bachynski-Polić and Yuna Zhao and Stian Fiskvik: Effect of floater flexibility on global dynamic responses of a 15-MW semi-submersible floating wind turbine. 2023.
- Hirvoas, A.: Model construction of Zefyros floating offshore wind turbine. 2022.
- Hobbacher, AF and others: Recommendations for fatigue design of welded joints and components. 2016.
- Homb, Hans Ranøyen: Fatigue Analysis of Mooring Lines on the Floating Wind Turbine Hywind Demo. 2013.
- IRENA: World Energy Transitions Outlook 2023: 1.5°C Pathway. 2023.
- Johnson, Nicholas and Jonkman, Jason and Wright, A and Hayman, Greg and Robertson, A: Verification of floating offshore wind linearization functionality in OpenFAST. 2019.
- Jonkman, Jason: TurbSim User's Guide v2.00.00 . 2016. chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/https://www.nrel.gov/wind/nwtc/assets/downloads/TurbSim/TurbSim_v2.00.pdf
- Jonkman, Jason Mark and Buhl, Marshall L and others: FAST user's guide. 2005.

- Jonkman, Jason M and Robertson, AN and Hayman, Greg J: HydroDyn user's guide and theory manual. 2014.
- Joyce Lee, Feng Zhao: Global wind report 2021. 2021. <https://gwec.net/wp-content/uploads/2021/03/GWEC-Global-Wind-Report-2021.pdf>
- V. Leroy and E.E. Bachynski-Polić and A. Babarit and P. Ferrant and J.-C. Gilloteaux: A weak-scatterer potential flow theory-based model for the hydroelastic analysis of offshore wind turbine substructures. 2021.
- Malenica, Š and Tuitman, Johan and Bigot, Fabien and Sireta, Francois-Xavier: Some aspects of 3D linear hydroelastic models of springing. 2008.
- Malenica, Š and Derbanne, Quentin and Sireta, Francois-Xavier and Bigot, Fabien and Tiphine, Etienne and De Hauteclocque, Guillaume and Chen, Xiao-Bo: HOMER—Integrated hydro-structure interactions tool for naval and offshore applications. 2013.
- Masjedian, M.H. and Keshmiri, Mehdi: A review on operational modal analysis researches: Classification of methods and applications. 2009.
- Molin, Bernard: Offshore structure hydrodynamics. 2023.
- National Renewable Energy Laboratory (NREL): OpenFast. 2024. <https://github.com/OpenFAST>
- Nava, V. and Ruiz-Minguela, P. and Perez-Moran, G. and Rodriguez Arias, R. and Lopez Mendia, J. and Villate-Martinez, J.-L.: Installation, Operation and Maintenance of Offshore Renewables. 2019.
- Oliveira, Gustavo and Magalhães, Filipe and Cunha, Álvaro and Caetano, Elsa : Continuous dynamic monitoring of an onshore wind turbine. 2018.
- Pastor, Miroslav and Binda, Michal and Harčarik, Tomáš : Modal Assurance Criterion. 2012.
- Redoute, T.: S-MORPHO system user manual. 2020.
- Ren21, K: Renewables 2021-Global Status Report: Tech. Rep.. 2021.
- Simulation Optimisation Parameters Package (Version 1.0) [Software] <https://gitlab.france-energies-marines.org/Romain/simuoptuna>
- Schlechtingen, Meik and Santos, Ilmar Ferreira and Achiche, Sofiane: Wind turbine condition monitoring based on SCADA data using normal behavior models. Part 1: System description. 2013.
- Schlechtingen, Meik and Santos, Ilmar Ferreira: Wind turbine condition monitoring based on SCADA data using normal behavior models. Part 2: Application examples. 2014.
- SERCEL: S-MORPHO system – Specifications of calculation algorithms. 2024.
- Sjur Neuenkirchen Godø: Dynamic Response of Floating Wind Turbines. 2013.
- Skaare, Bjørn and Hanson, Tor and Nielsen, Finn and Yttervik, Rune and Hansen, Anders and Thomsen, Kenneth and Larsen, Torben and Skaare@hydro, Bjorn and No, and David, Tor and No, Finn and Gunnar, and Com, Rune and No, Anders and Melchio: Integrated dynamic analysis of floating offshore wind turbines. 2007.
- Skaare, Bjørn and Nielsen, Finn and Hanson, Tor and Yttervik, Rune and Havmøller, Ole and Rekdal, Arne: Analysis of measurements and simulations from the Hywind Demo floating wind turbine: Dynamic analysis of the Hywind Demo floating wind turbine. 2014.
- Skaare, Bjørn and Nielsen, Finn and Hanson, T.D. and Yttervik, Rune and Havmøller, Ole and Rekdal, A.: Analysis of measurements and simulations from the Hywind Demo floating wind turbine. 2015.
- Stadtmann, Florian and Rasheed, Adil and Kvamsdal, Trond and Johannessen, Kjetil André and San, Omer and Kölle, Konstanze and Tande, John Olav and Barstad, Idar and Benhamou, Alexis and Brathaug, Thomas and Christiansen, Tore and Firle, Anouk-Letizia and Fjeldly, Alexander and Frøyd, Lars and Gleim, Alexander and Høiberget, Alexander and Meissner, Catherine and Nygård, Guttorm and Olsen, Jørgen and Paulshus, Håvard and Rasmussen, Tore and Rishoff, Elling and Scibilia, Francesco and Skogås, John Olav: Digital Twins in Wind Energy: Emerging Technologies and Industry-Informed Future Directions. 2023.
- Suja-Thauvin, Loup and Krokstad, Jørgen R. and Bachynski, Erin E. and Erik-Jan: Experimental results of a multimode monopile offshore wind turbine support structure subjected to steep and breaking irregular waves. 2017.
- Susan Gourvenec: Floating wind farms: how to make them the future of green electricity. 2020.
- Thomsen, Jonas Bjerg and Bergua, Roger and Jonkman, Jason and Robertson, Amy and Mendoza, Nicole and Brown, Cameron and Galinos, Christos and Stiesdal, Henrik: Modeling the TetraSpar Floating Offshore Wind Turbine Foundation as a Flexible Structure in OrcaFlex and OpenFAST. 2012.
- UNITECH: Dynamic cables for offshore wind farms. 2022. <https://www.techtransfer.no/en/renewable-energy/unitech/>
- van Vondelen, A. A. W. and Navalkar, S. T. and Iliopoulos, A. and van der Hoek, D. C. and van Wingerden, J.-W.: Damping identification of offshore wind turbines using operational modal analysis: a review. 2022.
- WindEurope: Floating Offshore Wind. 2020.
- WindEurope: Wind Energy in Europe: 2021 Statistics and the Outlook for 2022-2026. 2021. <https://windeurope.org/intelligence-platform/product/wind-energy-in-europe-2021-statistics-and-the-outlook-for-2022-2026/>
- WWEA: World Market for Wind Power Saw Another Record Year in 2021: 97,3 Gigawatt of New Capacity Added. 2019. <https://wwindea.org/world-market-for-wind-power-saw-another-record-year-in-2021-973-gigawatt/>
- Xiaoming Ran and Vincent Leroy and Erin E. Bachynski-Polić: Hydroelastic response of a flexible spar floating wind turbine: Numerical modelling and validation. 2023.
- Xu, Kun and Zhang, Min and Shao, Yanlin and Gao, Zhen and Moan, Torgeir : Effect of wave nonlinearity on fatigue damage and extreme responses of a semi-submersible floating wind turbine. 2019.
- Zhang, Lixian and Shi, Wei and Karimirad, Madjid and Michailides, Constantine and Jiang, Zhiyu: Second-order hydrodynamic effects on the response of three semisubmersible floating offshore wind turbines. 2020.
- Zhixin Zhao and Wenhua Wang and Wei Shi and Shengwenjun Qi and Xin Li: Effect of floating substructure flexibility of large-volume 10 MW offshore wind turbine semi-submersible platforms on dynamic response. 2022.